BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Estimate Cost Rs. 4000000.00

Name of Work: Detailed Estimate for the work of Drilling of borewells and maintenance works in ward no-02.

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	BOREWELL MAINTENANCE WORK PART (A).								
1	Lifting of Submersible Pump set (P,46/I.10.3.21 RDED SR (2002-03)	No	20				20	750.00	15000.00
2	Transportataion of pumping machineries (P.46/I.103)RDED SR (2002-03)	No	20				20	800.00	16000.00
3	**A) Repairs to Motor:**Rewinding of submersible pump sets with copper insulation wire of suitable gauge as per ISI specification with guarantee of 6months. RDED SR (2002-03)P NO.39/ I,NO.A)								
	a) -Do - above 3HP upto 5HP	No	20				20	2600.00	52000.00
	b) -Do - above 5HP upto 10HP	No	6				6	3800.00	22800.00
	(Above 5HP upto 10HP add Rs.120/- for every 1/2 HP)								
	B) Replacement of Motor Parts:								
4	Above 5HP Stator (with one year Gurantee) P.No.40/Ino.C(2)RDED SR (2002-03)	No	20				20	4800.00	96000.00
5	Above 5HP Rotor (with one year Gurantee) P.No.40/I No.C(2)RDED SR (2002-03)	No	20				20	4500.00	90000.00
6	Upper Flange P.No.40/I No.3 RDED SR (2002-03)	No	20				20	375.00	7500.00
7	Lower Housing P.No.40/I No.4 RDED SR (2002-03)	No	20				20	650.00	13000.00
8	Lower Flange P.No.40/I No.5 RDED SR (2002-03)	No	20				20	375.00	7500.00
9	a) Carbon Housing P.No.40/I No.7A RDED SR (2002-03)	No	20				20	500.00	10000.00
10	b) Thrust bearing block assembly complete with Segment bearing pad P.No.40/I No.7B RDED SR (2002-03)	No	20				20	1150.00	23000.00
11	c) Tip Carbon /Ferrodo pading P.No.40/I No.7C RDED SR (2002-03)	No	20				20	150.00	3000.00
12	Bearing (Gun metal)Centrifugal cast Aluminium Bronze, bearing bush P.No.41/I No,9 RDED SR (2002-03)	No	20				20	430.00	8600.00
13	Motor Base with pin P.No. 41/ I No.11 RDED SR (2002-03)	No	20				20	480.00	9600.00
14	Re-erection charges of pumping machineries including overhauling and painting P.No.41/I No 13,RDED SR (2002-03)	No	20				20	850.00	17000.00

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
15	Labour Charge (overhauling Motor only) **P.No.41/ I No.15 RDED SR (2002-03)**	No	20				**20**	600.00	**12000.00**
16	C) Replacement of pump parts: The following main components of submersible pump sets requiring replacement Pump bowls **P.No.39 / I No B1 RDED SR (2002-03)**	No	20				**20**	650.00	**13000.00**
17	Intermediate piece (I.P) with IP leaded bronze bush **P.No. 44/ I No.B2 RDED SR (2002-03)**	No	20				**20**	650.00	**13000.00**
18	Oil seal **P.No. 44/ I No.B3 RDED SR (2002-03)**	No	20				**20**	75.00	**1500.00**
19	Oil seal steel bush **P.No. 39/ I No.B4 RDED SR (2002-03)**	No	20				**20**	85.00	**1700.00**
20	Guide vane Pno 39/I No B5 RDED (2002-03)	No	20				**20**	175.00	**3500.00**
21	Impeller (shell moulded with aluminium and Bonze) P No 39/ I no B6 RDED SR 2002-03	No	20				**20**	450.00	**9000.00**
22	a) Discharge outlet (D.O) Bearing D.O Steel Bush **P.No. 39/ I No.B7 RDED SR (2002-03)**	No	20				**20**	575.00	**11500.00**
23	b)D.O Bearing **P.No. 39/ I No.B7 RDED SR (2002-03)**	No	20				**20**	325.00	**6500.00**
24	Steel bush (D.O) steel bush) **P.No. 39/ I No.B8 RDED SR (2002-03)**	No	20				**20**	160.00	**3200.00**
25	Allen Screw **P.No. 40/ I No.9 RDED SR (2002-03)**	No	20				**20**	25.00	**500.00**
26	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) **P.No. 40/ I No.10 RDED SR (2002-03)**	No	20				**20**	1150.00	**23000.00**
27	Pump key (Stainless steel) **P.No. 40/ I No.11 RDED SR (2002-03)**	No	20				**20**	140.00	**2800.00**
28	Pump coupling (stainless steel) **P.No. 40/ I No.12RDED SR (2002-03)**	No	20				**20**	300.00	**6000.00**
29	Non - Return valve (NRV) assembly complete with rubber 'O' Ring **P.No. 40/ I No.13RDED SR (2002-03)**	No	20				**20**	1350.00	**27000.00**
30	Cabble guard **P.No. 40/ I No.14RDED SR (2002-03)**	No	20				**20**	175.00	**3500.00**
31	Strainer **P.No. 40/ I No.15RDED SR (2002-03)**	No	20				**20**	150.00	**3000.00**
32	Providing and fixing 50 mm dia heavy duty coller **SE RDED Approved rate**	No	20				**20**	130.00	**2600.00**

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
33	Supply & delivery at site brand new texmo/innoval/lubi/sabar /kalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers,	No							
	17.5HP 30 Stage		1				1	72126.00	**72126.00**
	Basic Rate	72126.00							
34	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings)	Rmtr							
			1	200.00			**200.00**	279.66	**55932.00**
	Basic Rate	279.66							
35	Providing & fixing heavy duty collar (P.NO-III, I NO-86, PRED 12-13 SR)		1	50.00			**50.00**	154.50	**7725.00**
	Basic Rate	150.00							
	3% area weightage	4.50							
	Total	**154.50**							
36	Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto	Mtr							
			1	400.00			**400.00**	188.70	**75480.00**

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
37	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,.	No.	1				1.00	14800.00	**14800.00**
38	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14)	Sqm	1	1100.00	20.00		**22000.00**	0.35	**7696.00**
	Basic Rate	0.33							
	6% area weightage	0.02							
	Total	**0.35**							
39	Providing & Fixing of clamps set and borewell cap to the pump (MR)	No's	1				1.00	690.00	**690.00**
40	Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve. (PWD SR 18-19,	No's	1	3.00			**3.00**	1016.95	**3051.00**
	Basic Rate	1016.95							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
41	Supplying and delivery of brand new best make Gate Valve of size mm as per IS: 778/84 with latest amendments with ISI mark . 50mm Gate Valve for distributer pipeline. 50mm dia (PWD SR 18-19, P.NO.XXVI, Sl.no, 661 Code No. 0164)	No's							
			1				1.00	1398.31	1398.00
	Basic Rate	1398.31							
42	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) (P.No - 564, I.No - 3, BWSSB SR 13-14)	Per length							
			1	45.00			45.00	93.28	4198.00
	Basic Rate	88.00							
	6% area weightage	5.28							
	Total	93.28							
43	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc,. Complete for basement out door type. (MR)	No's							
			3	1.00			3.00	475.00	1425.00
44	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP (P.NO - 526, I.NO - 13D (a), BWSSB SR 13-14)	No's							
			6	1.00			6.00	932.80	5597.00
	Basic Rate	880.00							
	6% area weightage	52.80							
	Total	932.80							
45	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... **P No. 32/I No 3b KPWD Electrical SR 2010-11**	No.							
	63 Amps		6	3.00			18.00		
							18.00	150.00	2700.00
46	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (	Mtr							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
			6	28.00			168.00	174.90	29383.00
	Basic Rate	165.00							
	6% area weightage	9.90							
	Total	174.90							
47	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces (P.NO - 554, I.NO - 12 (b), BWSSB SR 13-14)	Mtr							
			3	28.00			84.00	58.30	4897.00
	Basic Rate	55							
	6% area weightage	3.30							
	Total	58.30							
48	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm (P.NO - 555, I.NO - 15 (b), BWSSB SR 13-14)	Mtr							
			3	3.00			9.00	303.16	2728.00
	Basic Rate	286.00							
	6% area weightage	17.16							
	Total	303.16							
49	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc,. is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using	No's							
			1				1.00	1749.00	1749.00
	Basic Rate	1650.00							
	6% area weightage	99.00							
	Total	1749.00							
50	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc, (P.NO - 555, I.NO - 16 (b) , BWSSB SR 13-14)	No's							
			1				1.00	279.84	280.00
	Basic Rate	264.00							
	6% area weightage	15.84							
	Total	279.84							
51	Providing and fixing Gun Metal Gate wheel valve confirming to IS specification of approved make as per direction including all lead and lift etc,. Complete. 50mm dia (P.NO	No's							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
			1	3.00			3.00	778.04	2334.00
	Basic Rate	734.00							
	6% area weightage	44.04							
	Total	778.04							
52	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2 5 inches (P.NO - 521, I.NO - 2 (f), BWSSB SR 13-14)	No's							
			3				3.00	320.65	962.00
	Basic Rate	302.500							
	6% area weightage	18.15							
	Total	320.650							
53	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per	Cum							
			1	425.00	0.60	0.75	191.25		
							191.25	316.94	60615.00
	Basic Rate	299.00							
	6% area weightage	17.94							
	Total	316.94							
54	Providing and installing at site of work 63mm (0 662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 18-19)	Mtr							
			1	425.00			425.00		
							425.00	394.32	167586.00
	Basic Rate	372.00							
	6% area weightage	22.32							
	Total	394.32							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
55	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 7, I.NO - 2.11, PWD SR 18-19)	Cum							
			1	425.00	0.60	0.75	**191.25**		
							191.25	128.26	**24530.00**
	Basic Rate	121.00							
	6% area weightage	7.26							
	Total	128.26							
56	Public fountains including GI taps and all accossories	Nos							
			10				10.00	2500.00	25000.00
							Sub Total (A)		**1107182.00**
	DRILLING OF BOREWELL (PART-B)								
1	Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped,	Each BW							
			4				4	1938.46	**7754.00**
	Basic Rate	1882.00							
	3% area weightage	56.46							
	Total	**1938.46**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
2	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for	Rmtr							
	0 to 50 m		4	50.00			200.00	315.18	63036.00
	50 to 100 m		4	50.00			200.00	412.00	82400.00
	100 to 150 m		4	50.00			200.00	458.35	91670.00
	150 to 200 m		4	50.00			200.00	484.10	96820.00
	200 to 250 m		4	50.00			200.00	560.32	112064.00
	250 to 300 m		4	50.00			200.00	600.49	120098.00
	300 to 320 m								
3	Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/1993 and manufactured from hot rolled steel skelp/stripes in random length of 4 to 7 mtr both ends threaded	Rmtr							
			4	60.00			240.00	1364.75	327540.00
	Basic Rate	1325.00							
	3% area weightage	39.75							
	Total	**1364.75**							
4	Providing and fixing 250mm dia PVC pipe and as per specification and directions. (BWSSB SR 13-14, P.No.53 I no 1 of sl.no.11.)	Rmtr							
			4	10.00			40.00	1133.00	45320.00
	Basic Rate	1100.00							
	3% area weightage	33.00							
	Total	**1133.00**							
5	175 mm dia M.S. Casing cap (P.NO-III, I.NO-85, PRED 12-13 SR)	Each							
			4				4	103.00	412.00
	Basic Rate	100.00							
	3% area weightage	3.00							
	Total	**103.00**							
6	M.S Casing pipe collars 'C' Class (P.NO-III, I.NO-86, PRED 12-13 SR)	Each	4	9.00			36	154.50	5562.00
	Basic Rate	150.00							
	3% area weightage	4.50							
	Total	**154.50**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
7	Supply & delivery at site brand new texmo/innoval/lubi/sabar talanta/calamal/ aterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 17.50 HP 30 stage (P.NO-XXXXIII, I.NO-34, PWD SR 18-19)	No							
	17 5HP 30 Stage		4				4	72126.00	288504.00
	Basic Rate	72126.00							
8	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings)	Rmtr							
			4	200.00			800.00	279.66	223728.00
	Basic Rate	279.66							
9	Providing & fixing heavy duty collar (P.NO-III, I.NO-86, PRED 12-13 SR)								
			4	50.00			200.00	154.50	30900.00
	Basic Rate	150.00							
	3% area weightage	4.50							
	Total	**154.50**							
10	Supplying and drawing 3 core PVC Sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS: 8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto	Mtr							
			4	400.00			1600.00	188.70	301920.00

Amount
88504.00
3728.00
0900.00
920.00

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
11	Supplying & delivery at site brand new / Essen / Lotus [redacted]nsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,	No.							
			4				4.00	14800.00	59200.00
12	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14)	Sqm							
			4	1100.00	20.00		88000.00	0.34	29911.00
	Basic Rate	0.33							
	3% area weightage	0.01							
	Total	**0.34**							
13	Providing & Fixing of clamps set and borewell cap to the pump (MR)	No's							
			4				4.00	690.00	2760.00
14	Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve. (PWD SR 18-19,	No's							
			4	3.00			12.00	1016.95	12203.00
	Basic Rate	1016.95							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
15	Supplying and delivery of brand new best make Gate Valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark . 50mm Gate Valve for distributer pipeline 50mm dia (PWD SR 18-19,	No's					12.00	1398.31	16780.00
			4	3.00					
	Basic Rate	1398.31							
16	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) (P.No - 564, I.No - 3, BWSSB SR 13-14)	Per length							
			4	25.00			100.00	90.64	9064.00
	Basic Rate	88.00							
	3% area weightage	2.64							
	Total	90.64							
17	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc,. Complete for basement out door type. (MR)	No's							
			4	1.00			4.00	475.00	1900.00
18	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP (P.NO - 526, I.NO - 13D (a), BWSSB SR 13-14)	No's							
			4	1.00			4.00	906.40	3626.00
	Basic Rate	880.00							
	3% area weightage	26.40							
	Total	906.40							
19	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... **P No. 32/I No 3b KPWD Electrical SR 2010-11**	No.							
	63 Amps		4	3.00			12.00		
							12.00	150.00	1800.00
20	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (	Mtr							
			4	25.00			100.00	169.95	16995.00
	Basic Rate	165.00							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	3% area weightage	4.95							
	Total	169.95							
21	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces (P.NO - 554, I.NO - 12 (b), BWSSB SR 13-14)	Mtr							
			4	25.00			100.00	56.65	5665.00
	Basic Rate	55							
	3% area weightage	1.65							
	Total	56.65							
22	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm (P.NO - 555, I.NO - 15 (b), BWSSB SR 13-14)	Mtr							
			4	3.00			12.00	294.58	3535.00
	Basic Rate	286.00							
	3% area weightage	8.58							
	Total	294.58							
23	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc,. is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using	No's							
			4				4.00	1699.50	6798.00
	Basic Rate	1650.00							
	3% area weightage	49.50							
	Total	1699.50							
24	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc, (P.NO - 555, I.NO - 16 (b) , BWSSB SR 13-14)	No's							
			4				4.00	271.92	1088.00
	Basic Rate	264.00							
	3% area weightage	7.92							
	Total	271.92							
25	Providing and fixing Gun Metal Gate wheel valve confirming to IS specification of approved make as per direction including all lead and lift etc,. Complete. 50mm dia (P.NO	No's							
			4	3.00			12.00	778.04	9336.00
	Basic Rate	734.00							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	6% area weightage	44.04							
	Total	778.04							
26	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2 5 inches (P.NO - 521, I.NO - 2 (f), BWSSB SR 13-14)	No's							
			4				4.00	311.58	1246.00
	Basic Rate	302.500							
	3% area weightage	9.075							
	Total	311.575							
30	KPTCL Deposit charges	No's	4				4.00	10000.00	40000.00
							SUB TOTAL (B)		2019635.00
	SUPPLY WATER THROUGH WATER TANKER PART -C								
1	Supply of water through water tanker	Load							
	yelahanka old town area		10				10.00		
							10.00		
	for 1 day = 10 load								
	for 82 days (in summer time)		10	82.00			820.00		
							820.00	540.00	442800.00
							SUB TOTAL (C)		442800.00
							GRANT TOTAL (A)+(B) + (C		3569617.00
							GST 12%		428354.04
2	Miscelaneous and rounding off.								2028.96
								TOTAL	4000000.00

(Rupees Forty lakhs Only)

CERTIFICATE

1 The work spot has been inspected and the work is found necessary.

2 The Estimate is prepared as per the PRED SR 2018-19 and PW,P & IWTD SR 2013-14 and BWSSB Electrical SR 2013-14

3 The provisions were made in this estimate are necessary and adequate.

4 This works come under B.B M.P. limits.

Assistant Engineer

Executive Engineer
Yelahanka Division
Bangalore-64

Assistant Executive Engineer
Yelahanka Sub Division
Bangalore-64

Administrative Approval

Accorded For ..Rs:40.00Lac
Head of A/C.....P:1802
CER NO :.....212 Dt:..25-2-19

TA CE (YNK)

Technical Sanction

Accorded For ..Rs:40.00Lac
Head of A/C.....P:1802
CER NO :.....256 Dt:..25-2-19

TA CE (YNK)